

NOTICE OF DETERMINATION

To: Office of Planning and Research
1400 Tenth Street, Room 121
Sacramento, California 95814

From: Solano County Department of Resource Management
Public Works Engineering
675 Texas Street, Suite 5500
Fairfield, California 94533

FILED

X County Clerk
County of Solano

MAY 03 2016

Subject:

Filing of Notice of Determination in compliance with Section 21108 or 21152 of the Public Resources Code, Clerk of the Board of Supervisors of the County of Solano, State of California

Project Title:

Stevenson Bridge 23C0092 at Putah Creek Rehabilitation Project

Deputy Sandy Hoffert, Deputy

2016042001	Philip Seilhan	707-784-6075
State Clearinghouse Number (If submitted to Clearinghouse)	Lead Agency Contact Person	Area Code/Telephone/Extension

Project Location (include county):

The bridge is located along Stevenson Bridge Road in Solano County, which becomes County Road 95A in Yolo County.

Project Description:

Bridge Rehabilitation - Seismic assessment of the bridge showed that many of the existing structural components of the bridge are unable to withstand seismic loads without retrofitting. Flexural and shear demands exceeded the corresponding capacities, requiring retrofit or replacement of several structural members in order to meet safety requirements. Deficient components include the bridge railing, deck spalling and carbonation, deck drains, cracking of approach spans, and substandard south approach alignment. In addition, the hydraulic analysis determined the structure is scour critical and scour mitigation will be required to maintain the structural integrity of the bridge. Bridge rehabilitation work will be conducted on the deck, piers, abutments, bent caps, hanger column, retaining wall, concrete railings, and approach spans. Deck drains will be removed, reconstructed, and refinished. The concrete railing will also be refinished, and the spalled and delaminated concrete will be patched. A hanger column will be removed and reconstructed, and the arch ribs from the spring line to the first column will be fiber wrapped. Piers 1, 2, and 3 will also be fiber wrapped. The pier curtain wall will be removed and reconstructed at Piers 1 and 2. Two cast-in-drilled-holes (CIDH) piling and pier footing overlays will be constructed at Piers 1, 2, and 3, and two CIDH piling and caps will be placed behind the abutments. Exterior girders and bent caps will be bolstered. The retaining wall on the south side of the bridge will be reconstructed, and 10 feet of the approach span slab will be removed and reconstructed. Rock slope protection will be used to stabilize the creek bank around the abutments and prevent scour. Pier bents will have 5 to 7 feet of excavation immediately around them for installation of scour protection measures.

Road Approach Realignment - Stevenson Bridge Road will be realigned to eliminate two sharp turns just south and east of the bridge, one of which is a 90-degree curve. The roughly 1,000-foot realignment will go through an existing orchard and transition onto the existing road alignment near Strathgordon Lane. The realigned road will comply with County standards and provide for safer vehicle passage. Realignment of the south approach will require right of way (ROW) acquisition from one privately owned parcel, APN 0107-020-040. Fill will be needed to create the new roadway alignment. No buildings or other structures on the privately owned parcel will need to be relocated or removed as a result of the proposed realignment.

Staging Area - The area above the northeast creek bank between County Road 95A and the access road will be used as a staging area. General bridge construction equipment to be used includes, but is not limited to, haul trucks, backhoes, dump trucks, excavators, grade-alls, bulldozers, drilling equipment, water trucks, concrete delivery trucks, and service vehicles.

Access Road and Temporary Creek Crossing - An access road will be cut in east of the bridge, on the north bank of Putah Creek, to access Piers 1 and 2. A temporary access road splits off from the permanent road at the top of the slope to access Pier 3. The access road will be composed of gravel and allow construction equipment to access the creek bed and the underside of the bridge. A creek crossing will be constructed between Piers 1 and 2, using either culverts and fill or a temporary low-span bridge.

Traffic Detour - Road closure will be required during road construction and bridge rehabilitation work. Traffic will be detoured using a loop along Stevenson Bridge Road, Sievers Road, Pedrick Road, Russell Boulevard, and Road 95A, with a maximum length of 13.7 miles.

Utility Relocation - Overhead poles with electric and phone lines occur along the south bridge approach, cross Putah Creek parallel to each side of the bridge, and continue north of the bridge. It is uncertain whether the poles and lines will need to be relocated. If relocation is necessary, the utility companies will be required to move the utilities prior to construction.

This is to advise that Solano County Department of Resource Management has approved the above-described project on May 3, 2016 and has made the following determinations regarding the above described project:
(Date)

- 1. The project [will will not] have a significant effect on the environment.
- 2. An Environmental Impact Report was prepared for this project pursuant to the provisions of CEQA.
 A Negative Declaration was prepared for this project pursuant to the provisions of CEQA.
- 3. Mitigation measures [were were not] made a condition of the approval of the project.
- 4. A statement of Overriding Considerations [was was not] adopted for this project.
- 5. Findings [were were not] made pursuant to the provisions of CEQA.

This is to certify that the Negative Declaration with comments and responses and record of project approval is available to the General Public at:

The Solano County Department of Resource Management, Public Works Engineering, 675 Texas Street, Suite 5500, Fairfield, CA. 94533


Signature (Public Agency)

May 3, 2016
Date

Engineering Services Supervisor
Title

Document Posted From
5-03-16 to 07/01/16
Sandy Hobbart
Deputy Clerk of the Board